IDAHO COUNTY ROAD DEPARTMENT
4682 Highway 13
Kooskia, Idaho 83539

The Idaho County Road Department will be accepting bids for the purchase of 25,000 tons of crushed aggregate.

Fuel Price Adjustment. The base fuel index is the Idaho Transportation Department Monthly Fuel Index (Spokane terminal, No. 2 ultra-low sulfur clear diesel) last posted before bid opening. The current fuel index is the ITD Monthly Fuel Index for the month in which material is crushed. If the current fuel index exceeds 120% of the base fuel index, the County will pay the Contractor the amount by which the current fuel index exceeds 120% of the base fuel index, per gallon, multiplied by 0.36 gallons per ton crushed that month. If the current fuel index is less than 80% of the base fuel index, the County will receive a credit calculated the same way against 80% of the base fuel index. The Contractor shall submit monthly reports of tons crushed. Bids will be compared and awarded on unadjusted unit prices.

Bids must be turned into Kathy Ackerman, Idaho County Clerk, 320 West Main, Room 5, Grangeville, Idaho 83530 by 5:00 P.M., December 14, 2026, and will be opened at 9:00 A.M., December 15, 2026.

Idaho County requests that the bid be submitted with material stockpiled on contractor's site. The contractor's stockpile location shall be within 3 miles of the town of Clearwater, in Idaho County. Stockpiles must be within a secure area.

Stockpile will be removed by September 30, 2028.

Contractor shall provide a way to take samples and do quality control testing for proper rock specifications. The Contractor shall provide the County with copies of reports.

The appropriate Public Works Contractors License shall be required.

A 5% bid bond is required. The contract is to be completed by April 15, 2026, or bond will be forfeited.

Idaho County retains the right to purchase additional aggregate depending on bid prices.

Commissioners reserve the right to reject any or all bids.

Any questions may be directed to Guy Von Bargen, Road Supervisor at 208-926-4471.

Material	Quantity	Stockpile
5/8” Gravel, Maintenance	22,000 tons	Contractor site
3” Base rock	3,000 tons	Contractor site

Rock Specifications

5/8” Gravel, Maintenance		3” Base Rock	
Sieve Size	% Passing	Sieve Size	% Passing
5/8”	100%	3”	100%
1/2”	90 – 100%		
#4	45 – 79%	#4	20 – 50%
#8	30 – 50%		
#30	15 – 30%		
#200	10 – 16%		
SE	35 Minimum		